

## 902 Main St Ste 205 Belmar, NJ 07719

## **Estimate / Contract**

Date	Estimate #	
8/1/2018	376832	

Name / Address	
Max Khagham	
21W 16Th St. NYC	

P.O. No.	Project

Description	Qty / SF / LF	Rate	Total
Description of Work:  1St Floor:  1) Repair the parquet floor where it is missing.  2) Use buffing machine to remove scratches and clean up the floor (no sanding machines the buffer)  3) Finish with 03 coats water based poly satin finish.  2nd Floor:  1) We will do light sanding just enough to remove the existing stain using the belt generally 2) Stain the floors natural color to match with kitchen floors  3) Finish with 03 coats water based poly satin finish.  Paint:  01 Coat of Primer and 01 Coat of paint to cover paint splashed on walls and baseboot Total Cost  A \$1000.00 Deposit is required upon acceptance of project	ine is being used	2,850.00	2,850.00
Signature Date	Total		\$2,850.00